



मादी गाउँपालिका

गाउँ कार्यपालिकाको कार्यालय

थुमाकोडाँडा, कास्की
गण्डकी प्रदेश, नेपाल

आ.व.२०८१/०८२

सूचना न.०३ (प्राविधिक शाखा)

कोटेशन पेश गर्ने सम्बन्धी सूचना ।

प्रथम पटक प्रकाशित मिति: २०८२/०२/१८

उपरोक्त सम्बन्धमा यस मादी गाँउ कार्यपालिकाको कार्यालय ,थुमाकोडाँडा,कास्कीको वार्षिक स्वीकृत कार्यक्रम अन्तरगत वडा न. ४ मा Construction Of Majuwa Guyelghari Gairi Kharka Sadak Nirman निर्माण योजना भएकोले इच्छुक निर्माण कम्पनिहरूले Bill Of Quantity मा आफुले उपलब्ध गराउन सक्ने न्युनतम दर रेट उल्लेख गरि फर्म दर्ता, करचुताको प्रमाण पत्र (आ.व.२०८०/०८१),स्थायी लेखा न. वा मूल्य अभिवृद्धि करको प्रमाण पत्र सहित यो सूचना प्रकाशन भएको मितिले ७ (सात) दिन भित्र यस गाँउपालिकाको कार्यालयमा उपस्थित भई उक्त कामको दर रेटको कोटेशन (Quotation) पेश गर्नको लागि यो सूचना प्रकाशन गरिएको छ।

नोट:उक्त कार्यको Bill Of Quantity यस मादी गाँउपालिकाको web site:- www.madimunkaski.gov.np बाट प्राप्त गर्न सकिन्छ।

तपशिल:-

क्र.स.न.	मादी गा.पा.	कामको विवरण	लागत अनुमान (कन्टेन्जेन्सी र मू.अ.कर समेत)
१	Ward no. 04	Construction Of Majuwa Guyelghari Gairi Kharka Sadak Nirman	NRs. 4,96,585.63 /-

प्रमुख प्रशासकीय अधिकृत

धनेन्द्र मुजेल



मादी गाउँपालिका
गाउँ कार्यपालिकाको कार्यालय
धुमाकोडाँडा, कास्की



योजनाको नाम : Construction Of Majuwa Guyelghari Gairi Kharka Sadak Nirman
स्थान :- मादी ४ ; मादी गा.पा , कास्की

आ.व. :- २०८१/०८२

सि.नं.:

Bill Of Quantity

S.N.	Description of Works	Unit	Quantity	Rate	Rate In Word	Amount	Remark
1	Carrying out different Additional Material laboratory tests of construction material like cement, rod, sand, aggregate, concrete cubes ,bitumen etc. during construction work as per specification and direction.	PS	1	10000			
2	Project description board at construction site- making, fixing all complete work as per instruction	PS	1	5000			
3	Roadway Excavation in all types of soil as per drawing and technical specification, including removal of stumps and other deleterious matter, with all lifts and lead as per Drawing and instruction of the Engineer.	Cum	31.88				
4	Providing and soling stone in foundation in true line and level including filling of voids by local sand all complete as per drawing, specification.	Cum	18.76				
5	Plain Cement Concrete of grade M15 including supplying, mixing, placing, compact and cure concrete in foundation footings, tie- beams, columns, beams, lintels, slabs as per drawings, specification and instruction of site engineer.	Cum	20.13				
6	Providing and laying Plum Concrete (Boulder Mixed Concrete) as per Drawing and Specifications 60% M15 concrete and 40% boulders/stone using Mechanical Aids incl. formwork	Cum	11.80				
7	Dismantalling Work:Dismantalling of old steps,keep the stone at safe location and levelling/cutting the ground all complete as per instruction of site Engineer.	LS	1.00				
8	laying of (dismantalled old steps)hand pack Stone soling with 100 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical	Sqm	3.90				
				Total			
				Vat(13%)			
				Grand Total			

[Signature]

धनंजय भुजेल
प्रमुख प्रशासकीय अधिकृत